

BUDGET REQUEST FROM OXFORD LAFAYETTE COUNTY PUBLIC LIBRARY WAS PRESENTED. NO ACTION WAS TAKEN.


**ORDER: ACCEPT CONSTRUCTION CHANGE
ORDER FOR SEMP 36(1)**


Motion was made by David Rikard, duly seconded by Chad McLarty, to accept construction change order for SEMP 36(1).

The vote on the motion was as follows:

Supervisor Kevin Frye, voted yes
Supervisor Jeff Busby, voted yes
Supervisor David Rikard, voted yes
Supervisor Chad McLarty, voted yes
Supervisor Mike Roberts, voted yes

After the vote, President Busby, declared the motion carried, this the 15th day of July, 2019.


Jeff Busby, President
Board of Supervisors


Sherry Wall, Chancery Clerk

OFFICE OF STATE AID ROAD CONSTRUCTION
Mississippi Department of Transportation
CONSTRUCTION CHANGE REQUEST

Project No. SEMP-36(1)

County: Lafayette

Date: 8-Jul-19

ATTN: STATE AID ENGINEER
CCR NO. 11

The following changes on the above project with stations, quantities and items involved, are recommended for the reasons stated in detail:

- PROPOSED:**
- To add 150.0 CY Granular Material (LVM) (Class 4, Group C).
 - To add 50.0 Tons Crushed Stone.
 - To add 30.0 Tons Hot Mix Asphalt, 9.5-mm, MT Mixture.
 - To add 800.0 Tons Hot Mix Asphalt, 12.5-mm, MT Mixture.
 - To add 180.0 SY Concrete Sidewalk (8" Thickness).
 - To delete 1.000 mile of 6" Wide Thermoplastic Traffic Stripe (Skip Yellow) and to add 1.500 miles of 6" Thermoplastic Traffic Stripe (Continuous Yellow).
 - To add 253.0 SF of Thermoplastic Legend (White) (120 mil).
 - To delete 4,200.0 SY Solid Sodding and to delete 2,800.0 LF Temporary Silt Fence.

- REASONS:**
- Plan quantity of granular material on ramps was underestimated.
 - Amount of crushed stone added in CCR 10 was underestimated.
 - Per final haul tickets - plan quantity was slightly underestimated.
 - Additional thickness of 12.5-mm HMA is required at Roundabout A (Anderson Road), Roundabout B (Hwy. 314), and Roundabout D (College Road) to bring existing road grade up to allow for 1-1/2" overlay of 9.5-mm HMA. Also, the North FNC Access Drive will receive an additional lift of 12.5-mm HMA.
 - Concrete truck apron on interior island of Roundabout B (Hwy. 314) was widened to allow for larger vehicles who may use Hwy. 314.
 - Passing zones shown on the striping plans are being removed and entire project will now be double-yellow centerline (no passing).
 - Bike lane legend (25 in total) are being added at various spots between 35+00 and 157+00 in the paved shoulders.
 - Quantities of solid sod and temporary silt fence were overestimated.

ORIGINAL QUANTITY AND COST

Participating Items						
S-304-A	Granular Material (LVM)(Class 4, Group C)	5,695.0 Ton	@	\$31.00	=	\$176,545.00
S-304-D	Crushed Stone	7,800.0 Ton	@	\$36.00	=	\$280,800.00
S-403-A	Hot Mix Asphalt, 9.5-mm, MT Mixture	1,570.0 Ton	@	\$98.70	=	\$154,959.00
S-403-A	Hot Mix Asphalt, 12.5-mm, MT Mixture	8,870.0 Ton	@	\$92.40	=	\$819,588.00
S-608-A	Concrete Sidewalk (8" Thickness)	713.0 SY	@	\$81.40	=	\$58,038.20
S-621-D	6" Wide Thermoplastic Traffic Stripe (Skip Yellow)(90 mil	1,100 MI	@	\$1,890.00	=	\$2,079.00
S-621-E-2	6" Wide Thermoplastic Traffic Stripe (Cont. Yellow)(90 m	6,000 MI	@	\$4,200.00	=	\$25,200.00
S-621-H-2	Thermoplastic Legend (White)(120 mil)	1,303.0 SF	@	\$10.50	=	\$13,681.50
S-226-A	Solid Sodding	15,170.0 SY	@	\$4.00	=	\$60,680.00
S-233-A	Temporary Silt Fence (Type I)(AOS 0.15mm-0.84mm)	20,065.0 LF	@	\$4.00	=	\$80,260.00
TOTAL ORIGINAL QUANTITY AND COST						\$1,671,830.70

REVISED QUANTITY AND COST

Participating Items						
S-304-A	Granular Material (LVM)(Class 4, Group C)	5,845.0 Ton	@	\$31.00	=	\$181,195.00
S-304-D	Crushed Stone	7,850.0 Ton	@	\$36.00	=	\$282,600.00
S-403-A	Hot Mix Asphalt, 9.5-mm, MT Mixture	1,800.0 Ton	@	\$98.70	=	\$157,820.00
S-403-A	Hot Mix Asphalt, 12.5-mm, MT Mixture	9,870.0 Ton	@	\$92.40	=	\$893,608.00
S-608-A	Concrete Sidewalk (8" Thickness)	893.0 SY	@	\$81.40	=	\$72,690.20
S-621-D	6" Wide Thermoplastic Traffic Stripe (Skip Yellow)(90 mil)	0.100 MI	@	\$1,890.00	=	\$189.00
S-621-E-2	6" Wide Thermoplastic Traffic Stripe (Cont. Yellow)(90 m	7,500 MI	@	\$4,200.00	=	\$31,500.00
S-621-H-2	Thermoplastic Legend (White)(120 mil)	1,558.0 SF	@	\$10.50	=	\$16,338.00
S-226-A	Solid Sodding	10,870.0 SY	@	\$4.00	=	\$43,880.00
S-233-A	Temporary Silt Fence (Type I)(AOS 0.15mm-0.84mm)	17,265.0 LF	@	\$4.00	=	\$69,060.00
TOTAL REVISED QUANTITY AND COST						\$1,748,880.20

INCREASE IN CONSTRUCTION COST \$77,049.50

Total Estimated Project - Per Contract Estimate Dated:	10/10/2017	\$11,326,100.00 (A)
Contingencies - Per Contract Estimate Dated:	10/10/2017	\$435,651.43 (B)
Total Contract Items (A - B)		\$10,890,448.57 (C)
Total Previously Approved Change Requests:	X Plus Minus	\$184,403.19 (D)
New Total - Contract Items (C+/-D)		\$11,054,851.76 (E)
Estimated Amount - This Request:	X Plus Minus	\$77,049.50 (F)
Revised Contract Items (E+/-F)		\$11,131,901.26 (G)
Indicated Underrun (A - G)		\$194,198.74
Indicated Overrun (G - A)		

APPROVAL RECOMMENDED: _____

County Engineer

APPROVAL RECOMMENDED: _____

District Engineer

APPROVED: _____

State Aid Engineer