ORDER: AUTHORIZE PROPOSED CHANGE ORDER #14 FOR THE NEW LAFAYETTE COUNTY SHERIFF'S DEPARTMENT TO ADD A CAST-IN-PLACE REINFORCED CONCRETE FOOTING AND FULLY GROUTED AND REINFORCED CMU STRUCTURAL BACKUP FOR THE WALL AT THE ENTRY PLAZA STAIRS

Motion was made by Scott Allen, duly seconded by Tim Gordon, to authorize Proposed Change Order \$14 for the new Lafayette County Sheriff's Department to add a cast-in-place reinforced concrete footing and fully grouted and reinforced CMU structural backup for the wall at the entry plaza stairs.

The vote on the motion was as follows:

Supervisor Brent Larson, absent Supervisor John Morgan, voted yes Supervisor Tim Gordon, voted yes Supervisor Scott Allen, voted yes Supervisor Greg Bynum, voted yes

After the vote, President Larson, declared the motion carried, this the 5th day of May, 2025.

Greg Bynum, Vice president

Board of Supervisors

Mike Roberts, Chancery Clerk



April 16, 2025

Joel Hollowell, Director of Development Services Lafayette County 300 North Lamar Boulevard Oxford, MS 38655

RE:

A New Sheriff's Department Building and Improvements at the Detention Center—Phase 2 (Rebid 2) Lafayette County Board of Supervisors PCO #14 - South Wall at Entry Plaza Stair

Dear Joel:

I attach the Contractor's PCO #14 to add a cast-in-place reinforced concrete footing and fully grouted and reinforced 8-inch CMU wall along the south side of the entry plaza stair, as indicated in RFP#8 (also attached). This Change was necessary to provide structural support for the brick veneer and cast stone copings at that location. All of the brick and cast stone are indicated on the architectural drawings and included in the Contract, but the concrete footing and structural portion of the wall at the entry plaza stair were inadvertently omitted from the structural drawings during the Construction Documents phase.

The Contractor's total proposed Change to the Contract Sum is \$12,631.61 with no additional Days included in this PCO to perform the additional work. We have reviewed the proposed costs, found them to be reasonable, and recommend that this proposal be accepted as soon as possible.

Please advise if you have any questions.

Sincerely yours.

Paul A. Waddell, Assoc. AIA

Senior Project Manager

Howorth & Associates Architects

Enclosures



2006 ASPEN COVE - BRANDON, MS - 39042 PHONE: (601) 824-4646 FAX: (601) 824-2211 www.flagstarconstruction.com

April 7, 2025

Attn: Paul Waddell Howorth and Associates Architects 800 North Lamar, Suite 4 Oxford, MS 38655

Re: LCSD Building and Improvements- Phase 2 Oxford, Mississippi

Change Proposal 014- Revised

Mr. Waddell:

Please accept the following as our proposal for costs associated with construction of the fully grouted CMU wall at the south side of the plaza entry steps per RFP NO. 8. The total cost is as follows:

•	Ideal Concrete (Proposal Attached)	\$5,950.00
	Bush Masonry (Proposal Attached)	
	Sales Tax (3.5%)	
	Subtotal	
	P&O (5%)	
	Total	

This proposal expires in fourteen (14) days. Please provide approval status as soon as possible.

Please do not hesitate to call me if you have any questions or need any additional information regarding the above.

Sincerely,

FLAGSTAR CONSTRUCTION COMPANY, INC.



R. Lee Kittrell Project Manager



Change Order for Wall LCSD

April 1, 2025

•	Footing	price	for w	ingwall	at	entry	plaza	stairs

• Excavate footing, place rebar, pour and finish concrete

Total Price......\$5,950

Thank you,

Brandon Voyles

Owner/President

Ideal Concrete Finishing, INC.

Voylesbrandon@yahoo.com

Paul Waddell	
From: Sent: To: Subject:	Paul Waddell Wednesday, April 09, 2025 9:00 AM Paul Waddell FW: Change order Footing Detailed breakdown
From: Lee Kittrell < lee@flagstard Sent: Wednesday, April 09, 2025 To: Paul Waddell < paul@howort Subject: Fwd: Change order Foot	8:12 AM harch.com>
	Ideal. The footing will only require 4cy with waste, however the concrete e for deliveries less than 6cy.
Thanks,	
R. Lee Kittrell, <i>LEED®-AP</i>	
Flagstar Construction Com	pany, Inc.
2006 Aspen Cove	
Brandon, <u>MS 3</u> 9042	
601-824-4646	
Fax 601 <u>-824-3929</u>	
Cell 601-209-7982	
lee@flagstarconstruction.c	om

Begin forwarded message:

From: Kyler Dillard < codykylerdillard 17@gmail.com >

Date: April 8, 2025 at 2:19:19 PM CDT

To: Lee Kittrell < lee@flagstarconstruction.com > Subject: Change order Footing Detailed breakdown

Concrete-\$1,091 for 6 yards Rebar for footing and blocks-\$909 Machine-\$545 Labor-\$2,864 P&O (10%)-\$541

Grand total-\$5,950

Change Proposal

Bush Masonry, LLC

3705 Classic Drive S. Memphis, TN 38125

Phone: 901-258-1070

/6/2025	Date temized 4								<u>-</u> -	MS	etment Oxford	New Sheriff's Dep	
											artinetti Oxford		Job Name
												Flagstar	ro.
				OTHERS)	ovided BY	erial is p	rebar mat	iaza (masonr)	J @ South P	fed CM	RFP 08 Add	inption of Change	Name and/or Descr
Extension	Labor			ž.	nent/Other	Equip			/aterial	,			
	Cost	Unit	Quantity	Extension	Cost	Unit	Quantity	Extension	Cost	Unit	Quantity	n of Items	Description
								\$1 732.50	5 7 50	each	231 00	and accys	CMU (incl. mortar, wire a
\$1 380	\$33.75	1 2						\$820.00	\$205.00	cuyd	4 00		out Block Fill (minimum o
\$820	\$25.65	hour	32										son Labor
		, (OU)	32	\$480.00	\$15 00	11000	32.00						son Tender Labor ntractor Owned Equipme
\$1,900	Labor Subtotal							\$2,552.50 \$0.00	nal Subtotal	Mate es Tax	Sal		
\$1,900	Labor Costs Total			\$480.00	nent Total	Equip		\$2,552.50	s including s Tax Total		Mater		
\$2,552 \$480				<u></u>									
\$4,933				Market									
\$740				M+E+L OH&P									
\$5,673			_	Uner									
\$5,673.			hange	Total C									



PROFESSIONAL'S REQUEST FOR PRICING

PROJECT: A New Sheriff's Department Building and

Improvements at the Detention Center—Phase 2 (Rebid 2)

Lafayette County Board of Supervisors

Oxford, Mississippi

PROJECT NO: 2020-30-2

RFP NO. 8

DATE: March 31, 2025

PLEASE PROVIDE AN !TEMIZED PROPOSAL THAT INCLUDES THE FOLLOWING:

Item No. 1 — Furnish all materials and labor required to add cast-in-place reinforced concrete footing and fully grouted and reinforced 8-inch CMU structural backup for S. wingwall at entry plaza stair, as indicated on attached Supplemental Drawing SD-09 dated 3/31/25.

